

# Application of AtoN Telematics for Structural Health Monitoring

Aivar Usk, Cybernetica AS

Per Erik Ose, Norwegian Coastal Administration

Leif Arne Larsen, Norwegian Coastal Administration

© Cybernetica AS and the Norwegian Coastal Administration

# Problem

- ⊙ Structural stability of certain types of fixed AtoN platforms is degrading at less predictable rate than others
- ⊙ Stability of lattice masts and seabed-embedded poles is subject to degradation due to wind and wave effects
- ⊙ Cases of **fixed AtoN platforms collapsing under wind or wave load, or introducing permanent focal plane inclination / misalignment of leading line centerline** due to material degradation are not too rare
- ⊙ Restoration of a collapsed AtoN tends to be costly while safety of navigation is at least temporarily compromised

# Solution

- ⊙ Responding with slight deflection to external excitations like incident wind gusts and waves, slender pole-like structures tend to **vibrate at clearly defined natural frequencies** that shift when mechanical properties of the structure change (loose bolts or tensioners, weight loss)
- ⊙ That effect presents opportunities for two-tiered structural health monitoring of AtoN platforms:
  - ⊙ Monitoring of the **vibration magnitude** to estimate severity of conditions and detect trends like increasing deflections
  - ⊙ Monitoring of the **frequency** of the dominating spectral component in order to detect mechanical changes

# Natural Frequency Appears When Excited



The resonance frequency depends on mass, stiffness and damping: dimensions, materials, weight, temperature, etc

# Applicable Technologies

- ① **Structural Health Monitoring (SHM)** is nothing new
- ① Optimal for use on AtoN: an in-situ **acceleration sensor**
- ① **Analysis of vibration spectra using the Fast Fourier Transform (FFT)** may require too much **power** locally; it can be performed automatically at the server side after uploading the acceleration data from an AtoN site
- ① Cost savings come from tasking the **AtoN telematics infrastructure** with additional monitoring mission

# Cybernetica AtoN SHM Solution

- ⊙ Based on existing AtoN Telematics Controller **TelFiCon™** that uses a triaxial solid state acceleration sensor
- ⊙ In-situ **acceleration measurement with local inclination angle calculation and raw data upload** to the telematics server since 2008 (GSM/GPRS/3G)
- ⊙ Widely configurable measurement mission profile: from 1 minute hourly sessions to continuous acceleration measurement at **20 ms sampling interval**
- ⊙ Temperature and voltage measurement as standard, AtoN **flasher functionality supporting FFI** is available

# NCA01: Dirigens Lux AtoN at Småge




- Height 7.5 m above sea level, 2 m under water (high tide)
- Weight 100 kg
- Mount: embedded in seabed (or rock)
- Bearing structure: Ø 140 mm composite rod
- Type: Test object for a new maintenance free large composite HIB AtoN design



# NCA02: Dirigens Mini AtoN at Sandøy




- Height 6.5 m above sea level, 0.5 m below (high tide)
- Weight 60 kg
- Mount: embedded in seabed (or rock)
- Bearing structure: Ø 140 mm composite rod
- Type: Test object for a new maintenance free small composite HIB AtoN



# NCA03: Original HIB AtoN at Nørve




- Height 8.5 m above sea level, 1.5 m below at high tide
- Weight 500 kg
- Mount: embedded in seabed (or rock)
- Bearing structure: Ø 140 mm steel rod
- Type: Test object for the initial HIB design, large metal structure



# NCA04: Lighthouse at Husøyvågen, Ona




- ⊙ Height 8 m above ground
- ⊙ Weight 1500 kg
- ⊙ Mount: 4 x threaded rods 48x1000 VZN
- ⊙ Bearing structure: Composite GRP




# NCA05: Litus Lux Lighthouse on Svalbard



- Height 6.5 m
- Weight 500 kg
- Mount: 4 threaded rods 48x1000 VZN
- Bearing structure: Ø 800 mm Glass fiber reinforced vinylester with a core of Divynccell
- Type: Test object for a new maintenance free generation of composite Lighthouses



# NCA05: Litus Lux Lighthouse Environment




Inclination changes at 1.25° average are insignificant, within measurement uncertainty

17.11.2014 12

CYBERNETICA

# NCA05: Litus Lux Lighthouse Acceleration

NCA05 acceleration maxima recorded in horizontal plane




Incident wind gusts cause deflections of even stiff structures, up to 0.2g for NCA05

17.11.2014 13

CYBERNETICA

# NCA05: Litus Lux Lighthouse Vibrations

NCA05 dominating vibration spectra component RMS amplitudes calculated for all axes




Resulting wind induced vibrations are clearly detectable and in correlation with weather data

17.11.2014 14

CYBERNETICA

# NCA05: Litus Lux Natural Frequency

## X-Axis vibration frequency and magnitude (RMS)




Natural frequency ~7 Hz manifests itself when external excitation exceeds certain threshold

17.11.2014 15

CYBERNETICA

# NCA05: Vibration Amplitude & Frequency




Looking at nearly 2 months of dominant frequency (X) using FFT reveals very little changes

17.11.2014 16

CYBERNETICA

# NCA05: Vibration Amplitude & Frequency




Setting a 1 mg threshold for displaying the results cleans away irrelevant noise at quiet times

17.11.2014 17

CYBERNETICA

# NCA05: Vibration Amplitude & Frequency




Setting a 2 mg threshold for displaying the results reveals NCA05 natural frequency trends

17.11.2014 18

CYBERNETICA

# NCA05: Litus Lux Frequency Statistics

Statistical distribution of dominating frequency at the X-axis of NCA05, instances above 2 mg threshold [%]




In nearly 2 months the dominant frequency was rarely detected outside typical bins

17.11.2014 19

CYBERNETICA

# NCA05: Litus Lux Acceleration Spectrum

## NCA05 acceleration spectrum on X axis




Frequency content of FFT analysis: **noise** (light air, southwest 1.2 m/s, gusts 1.8 m/s, -1.2°C)

17.11.2014 20

CYBERNETICA

# NCA05: Litus Lux Acceleration Spectrum

## NCA05 acceleration spectrum on X axis (RMS)




Frequency: **6.1523 Hz** (fresh southwest breeze 9.2 m/s, gusts 13.2 m/s, 6.1°C)

17.11.2014 21

CYBERNETICA

# NCA05: Litus Lux Acceleration Spectrum

## NCA05 acceleration spectrum on X axis




Frequency: **6.0547 Hz** (strong west-southwest breeze 11.5 m/s, gusts 15.9 m/s, 1.4°C)

17.11.2014 22

CYBERNETICA

# NCA05: Natural Frequency Drift in Cold



While typical results for NCA05 natural frequency analysis averaged around **6.15 Hz** at positive temperatures, it increased to **6.69 Hz** in above case and even **7.4 Hz** below **-10°C**

17.11.2014 23

CYBERNETICA

# User Interface in Web Browser (PDA)

195.50.202.195



## Kystverket-Cyber TeViNSA™ LSC AtoN Telematics Server 2.11

Site Name	Last Session	Voltage [V]	Heel Angle [deg]	Position	Script	Vibration X   Y   Z
<a href="#">NCA01</a>	2014-11-06 10:53:29	<a href="#">12.95</a>	<a href="#">3.0</a>	<a href="#">On-site</a> <a href="#">T</a>	<a href="#">Accel_Meas_Custom (20:4)</a>	<a href="#">17</a>   <a href="#">8</a>   <a href="#">1</a>
<a href="#">NCA02</a>	2014-11-06 10:51:46	<a href="#">12.54</a>	<a href="#">1.9</a>	<a href="#">On-site</a> <a href="#">T</a>	<a href="#">Accel_Meas_Custom (20:4)</a>	<a href="#">4</a>   <a href="#">5</a>   <a href="#">1</a>
<a href="#">NCA03</a>	2014-11-06 10:51:49	<a href="#">14.15</a>	<a href="#">0.3</a>	<a href="#">On-site</a> <a href="#">T</a>	<a href="#">Accel_Meas_Custom (20:4)</a>	<a href="#">3</a>   <a href="#">3</a>   <a href="#">2</a>
<a href="#">NCA04</a>	2014-11-06 10:54:11	<a href="#">14.21</a>	<a href="#">1.4</a>	<a href="#">On-site</a> <a href="#">T</a>	<a href="#">Accel_Meas_Custom (20:4)</a>	<a href="#">0</a>   <a href="#">1</a>   <a href="#">1</a>
<a href="#">NCA05</a>	2014-11-06 09:59:16	<a href="#">12.72</a>	<a href="#">1.3</a>	<a href="#">On-site</a> <a href="#">T</a>	<a href="#">Accel_Meas_Custom (20:119)</a>	<a href="#">0</a>   <a href="#">2</a>   <a href="#">1</a>

Page refresh time: 06.11.2014 at 10:55:16 UTC+1

Server started at: 22.10.2014 at 14:34:10

[Server logfile](#) [Alarms logfile](#) [Heel angle and temperature logfile](#) [Last position of all AtoNs](#)

[TLSC setup](#)



# Measurement Results, September/October


AtoN ID	AtoN Type	Natural Frequency, X-axis [Hz]	Natural Frequency, Y-axis [Hz]	Peak Vibration Magnitude, X-axis [g]	Peak Vibration Magnitude, Y-axis [g]	Peak Acceleration, X-axis [g]	Peak Acceleration, Y-axis [g]	Maximum Inclination Angle Difference [°]
NCA01	Dirigens Lux, 100 kg	<b>0.68</b>	<b>0.68</b>	0.141	0.119	0.423	0.324	1.92
NCA02	Dirigens Mini, 60 kg	<b>1.66</b>	<b>1.51</b>	0.095	0.750	1.061	1.395	1.88
NCA03	Original HIB, 500 kg	<b>0.59</b>	<b>0.59</b>	0.094	0.095	0.221	0.266	2.33
NCA04	Standard composite lighthouse, 1500 kg	<b>5.96</b>	<b>5.18</b>	0.097	0.147	0.453	0.488	0.84
NCA05	Litus Lux composite lighthouse, 500 kg	<b>6.15</b>	<b>5.86</b>	0.016	0.030	0.129	0.198	0.24

All types of fixed AtoN subject to SHM testing by TelFiCon™ units provided meaningful data

17.11.2014 **25**

**CYBERNETICA**

# Collision Test on NCA02 on 2014-11-05




NCA02 AtoN platform acceleration and vibration magnitude peaks were recorded at 09:51

17.11.2014 26

CYBERNETICA

# NCA02 Collision Test Results of 2014-11-05



Vibration profile of the NCA02 AtoN platform was changed permanently by the collision: **the X natural frequency shifted from 1.66 Hz to 1.46 Hz**, higher frequency components changed

# Conclusions

- ⊙ Preliminary results of deployment of AtoN telematics controllers TelFiCon™ on the selected fixed AtoNs of the Norwegian Coastal Administration for SHM are useful

Application of fixed AtoN Structural Health Monitoring as described **increases navigational safety and optimizes corrective maintenance costs** by comprehensive watch:

- ⊙ platform **inclination angles** (two alarm thresholds)
- ⊙ horizontal and vertical **acceleration vector magnitudes**
- ⊙ **amplitudes** of dominant components of vibration spectra (two thresholds) with immediate and detailed FFT analysis
- ⊙ **frequency** of the dominant spectral component
- ⊙ **collision events** detected even at TelFiCon™ standby

# Additional Information

Information on this AtoN Structural Health Monitoring project and associated technology can be requested from:

Mr Per Erik Ose, [per.erik.ose@kystverket.no](mailto:per.erik.ose@kystverket.no)

Mr Leif Arne Larsen, [leif.arne.larsen@kystverket.no](mailto:leif.arne.larsen@kystverket.no)

Mr Aivar Usk, [aivar.usk@cyber.ee](mailto:aivar.usk@cyber.ee)

